# GH-18 · Revision R1 · Materials and quantities

Design-stage take-off from the 3D model (house_r1.json, tools/boq.py). Quantities only; wastage as stated; to be confirmed on site. The editable Excel file has every line: GH-18_R1_materials.xlsx.

## Summary

| | |
|---|---|
| **1. Tiles** | Wet-room walls 1376 sq ft; tiled floors 1643 sq ft (washrooms, servant room, store, balcony, terraces); 445 sq ft waterproofing |
| **Living floors** | Option A Italian marble 2104 sq ft net (+15% wastage = 2420 sq ft) \| Option B 1600 × 800 vitrified 86 boxes \| skirting 512 rft |
| **2. Pipes** | Drainage 76 m, water 102 m, rainwater 41 m (+ AC copper 45 m) |
| **3. Wires** | Power and lighting cable 3681 m, Cat-6 75 m, conduit 1302 m |
| **4. Paint** | Interior walls 3891 sq ft, ceilings 2535 sq ft, exterior 2738 sq ft; about 93 L interior emulsion, 51 L exterior |
| **5. POP** | False ceiling 2535 sq ft (120 gypsum boards), cove 592 rft |
| **6. Granite** | Counter tops 84 sq ft, 14 sills 56 sq ft, 24 thresholds 37 sq ft, stair 236 sq ft, flamed paving 147 sq ft |
| **7. Timber** | 15 door frames (22.7 cft) + 16 shutters; pergola 36.5 cft; handrail 43 rft; veneer cladding 684 sq ft; fluted walnut 301 sq ft |
| **8. MDF** | Wardrobes 72 sheets 18 mm + 24 sheets 8 mm; other storage 75 + 31; BWP ply (wet) 15 sheets; 369 soft-close hinges |
| **9. Lights** | 88 downlights (on 36 light points), 7 fans, 181 m cove LED, 9 m under-cabinet LED, 4 mirror, 10 wall, 8 garden lights |
| **10. uPVC** | 4 openings (GF rear wall, FF master balcony): frame 44 m, solar-control glass 183 sq ft (69 sq ft laminated), mosquito mesh 114 sq ft, MS grilles 126 sq ft |

## Rooms

| Floor | Room | Area sq ft | Floor | Marble A sq ft | Tiles B boxes | Wall paint sq ft | Wall tiles sq ft | POP sq ft | Cove rft | Lights |
|---|---|---|---|---|---|---|---|---|---|---|
| GF | Kitchen | 171 | Italian marble | 197 | 7 | 396 | | 171 | 56.0 | 7 downlights, 2 light points, 2 exhaust, 1 heat det. |
| GF | Dining | 149 | Italian marble | 171 | 6 | 240 | | 149 | 30.0 | 8 downlights, 2 light points, 1 pendant, 1 mirror light |
| GF | Family Lounge | 179 | Italian marble | 205 | 7 | 171 | | 179 | 38.0 | 8 downlights, 2 light points, 1 wall light, 1 fan, 1 smoke det. |
| GF | Lobby | 137 | Italian marble | 157 | 6 | | | 137 | 45.0 | 5 downlights, 2 light points, 1 smoke det. |
| GF | Toilet | 90 | Porcelain 1200×600 | | | | 315 | 90 | | 2 downlights, 2 light points, 1 exhaust |
| GF | Guest Room | 202 | Italian marble | 232 | 8 | 432 | | 202 | 57.0 | 6 downlights, 2 light points, 1 fan, 1 smoke det. |
| GF | Entrance Foyer | 60 | Italian marble | 69 | 3 | | | 60 | 32.0 | 2 downlights, 2 light points |
| GF | Guest Lounge / Study | 147 | Italian marble | 169 | 6 | | | 147 | 49.0 | 6 downlights, 2 light points, 1 fan, 1 smoke det. |
| GF | Under-stair Storage | 51 | Flamed granite | | | 230 | | | | 1 light points |

| | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| FF | Master Washroom | 55 | Porcelain 1200×600 | | | | 238 | 55 | | 1 downlights, 2 light points, 1 mirror light, 1 exhaust |
| FF | Dresser | 87 | Italian marble | 101 | 4 | 268 | | 87 | 37.0 | 2 downlights, 1 light points, 1 mirror light |
| FF | Master Bedroom | 275 | Italian marble | 316 | 11 | 408 | | 275 | 72.0 | 9 downlights, 3 light points, 1 fan, 1 smoke det. |
| FF | Balcony | 68 | Deck tile | | | | | | | 2 wall light, 2 garden light |
| FF | Bedroom 3 Toilet | 68 | Porcelain 1200×600 | | | | 253 | 68 | | 2 downlights, 1 light points, 1 mirror light, 1 exhaust |
| FF | Lobby | 99 | Italian marble | 114 | 4 | 232 | | 99 | 37.0 | 3 downlights, 2 light points, 1 smoke det. |
| FF | Bedroom 3 | 273 | Italian marble | 314 | 11 | 536 | | 273 | 71.0 | 9 downlights, 2 light points, 1 fan, 1 smoke det. |
| FF | Kids Room | 227 | Italian marble | 260 | 9 | 443 | | 227 | 67.0 | 9 downlights, 2 light points, 1 fan, 1 smoke det. |
| FF | Kids Toilet | 50 | Porcelain 1200×600 | | | | 237 | 50 | | 2 downlights, 1 light points, 1 exhaust |
| SF | Lobby | 99 | Italian marble | 114 | 4 | 217 | | 99 | | 3 downlights, 2 light points, 1 smoke det. |
| SF | Servant Washroom | 26 | Porcelain 1200×600 | | | | 141 | 26 | | 1 downlights, 1 light points, 1 exhaust |
| SF | Store | 39 | Porcelain 1200×600 | | | | 193 | 39 | | 1 downlights, 1 light points |
| SF | Servant Room | 102 | Vitrified 600×600 | | | 318 | | 102 | | 2 downlights, 1 light points, 1 fan, 1 smoke det. |
| SF | Back Terrace + Utility (covered) | 430 | Deck tile | | | | | | | 2 wall light |
| SF | Front Terrace (open) | 455 | Deck tile | | | | | | | |

## 1. Tiles

| Floor | Room / area | Surface | Material | Net m2 | Net sq ft | Wastage % | Boxes |
|---|---|---|---|---|---|---|---|
| GF | Toilet | Floor | Matte porcelain 1200 × 600 mm, warm grey (washrooms, floors + walls) | 8.37 | 90 | 10 | 7 |
| GF | Toilet | Walls (full height to the false ceiling) | Matte porcelain 1200 × 600 mm, warm grey (washrooms, floors + walls) | 29.28 | 315 | 10 | 23 |
| FF | Master Washroom | Floor | Matte porcelain 1200 × 600 mm, warm grey (washrooms, floors + walls) | 5.11 | 55 | 10 | 4 |
| FF | Master Washroom | Walls (full height to the false ceiling) | Matte porcelain 1200 × 600 mm, warm grey (washrooms, floors + walls) | 22.1 | 238 | 10 | 17 |
| FF | Balcony | Floor | Wood-look porcelain deck tile 1200 × 200 mm, R11 anti-skid (balcony, terraces) | 6.3 | 68 | 10 | 5 |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| FF | Bedroom 3 Toilet | Floor | Matte porcelain 1200 × 600 mm, warm grey (washrooms, floors + walls) | 6.36 | 68 | 10 | 5 |
| FF | Bedroom 3 Toilet | Walls (full height to the false ceiling) | Matte porcelain 1200 × 600 mm, warm grey (washrooms, floors + walls) | 23.46 | 253 | 10 | 18 |
| FF | Kids Toilet | Floor | Matte porcelain 1200 × 600 mm, warm grey (washrooms, floors + walls) | 4.65 | 50 | 10 | 4 |
| FF | Kids Toilet | Walls (full height to the false ceiling) | Matte porcelain 1200 × 600 mm, warm grey (washrooms, floors + walls) | 22.02 | 237 | 10 | 17 |
| SF | Servant Washroom | Floor | Matte porcelain 1200 × 600 mm, warm grey (washrooms, floors + walls) | 2.43 | 26 | 10 | 2 |
| SF | Servant Washroom | Walls (full height to the false ceiling) | Matte porcelain 1200 × 600 mm, warm grey (washrooms, floors + walls) | 13.06 | 141 | 10 | 10 |
| SF | Store | Floor | Matte porcelain 1200 × 600 mm, warm grey (washrooms, floors + walls) | 3.64 | 39 | 10 | 3 |
| SF | Store | Walls (full height to the false ceiling) | Matte porcelain 1200 × 600 mm, warm grey (washrooms, floors + walls) | 17.92 | 193 | 10 | 14 |
| SF | Servant Room | Floor | Vitrified 600 × 600 mm, light (SF service rooms) | 9.46 | 102 | 8 | 8 |
| SF | Back Terrace + Utility (covered) | Floor | Wood-look porcelain deck tile 1200 × 200 mm, R11 anti-skid (balcony, terraces) | 39.96 | 430 | 10 | 31 |
| SF | Front Terrace (open) | Floor | Wood-look porcelain deck tile 1200 × 200 mm, R11 anti-skid (balcony, terraces) | 42.27 | 455 | 10 | 33 |
| GF | Deck + Pergola | Floor | Wood-look porcelain deck tile 1200 × 200 mm, R11 anti-skid (balcony, terraces) | 24.1 | 259 | 10 | 19 |

## 2. Pipes

| Kind | Dia mm | Specification | Length m | Length ft | 3 m lengths (+10%) | Bends (approx.) | Runs / items |
|---|---|---|---|---|---|---|---|
| cold | 25 | CPVC SDR 11, 1" (25 mm) | 34.1 | 111.8 | 13 | 9 | 9 |
| cold | 32 | CPVC SDR 11, 1 1/4" (32 mm) | 50.9 | 167.1 | 19 | 16 | 4 |
| hot | 25 | CPVC SDR 11, 1" (25 mm), hot | 17.5 | 57.3 | 7 | 5 | 2 |
| rain | 100 | uPVC SWR 110 mm (rainwater) | 40.6 | 133.3 | 15 | 1 | 7 |
| sewer | 110 | uPVC SN8 110 mm, underground | 4.9 | 16.1 | 2 | 1 | 1 |
| sewer | 150 | uPVC SN8 150 mm, underground | 18.0 | 58.9 | 7 | 4 | 4 |
| soil | 110 | uPVC SWR 110 mm, Type B, ring-fit | 29.5 | 96.7 | 11 | 2 | 7 |
| waste | 50 | uPVC SWR 50 mm, Type A | 3.3 | 10.9 | 2 | 1 | 3 |
| waste | 75 | uPVC SWR 75 mm, Type A | 20.7 | 68.1 | 8 | 12 | 8 |
| chamber | | IC-2 inspection: OTS, 600×600 mm, 700 deep | | | | | 1 |
| chamber | | GT-1 grease trap: OTS, 450×450 mm, 500 deep | | | | | 1 |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| chamber | | CO-1 cleanout: GF lobby, 300×300 mm, 500 deep | | | | | 1 |
| chamber | | CO-2 cleanout: GF lobby / foyer, 300×300 mm, 580 deep | | | | | 1 |
| chamber | | IC-3 inspection: entrance court, 600×600 mm, 800 deep | | | | | 1 |
| chamber | | IC-4 inspection: parking, 600×600 mm, 700 deep | | | | | 1 |
| chamber | | IC-5 inspection: parking, 600×600 mm, 900 deep | | | | | 1 |
| chamber | | RWH rwh pit: entrance court, 1200×1200 mm, 2000 deep | | | | | 1 |
| chamber | | VB-1 valve box: front lawn, by the gate, 600×450 mm, 450 deep | | | | | 1 |
| refrigerant | | Copper pair 1/4" + 5/8" insulated, 2 TR AC GF-DRW → SF-AC3 (+ 20 mm PVC drain, 4C x 1.5 sq mm interconnect) | 11.0 | 36.1 | | | 1 |
| refrigerant | | Copper pair 1/4" + 5/8" insulated, 2 TR AC FF-MST → SF-AC4 (+ 20 mm PVC drain, 4C x 1.5 sq mm interconnect) | 2.7 | 8.7 | | | 1 |
| refrigerant | | Copper pair 1/4" + 1/2" insulated, 1.5 TR AC FF-BD3 → SF-AC1 (+ 20 mm PVC drain, 4C x 1.5 sq mm interconnect) | 15.7 | 51.7 | | | 1 |
| refrigerant | | Copper pair 1/4" + 1/2" insulated, 1.5 TR AC FF-KID → SF-AC5 (+ 20 mm PVC drain, 4C x 1.5 sq mm interconnect) | 3.5 | 11.4 | | | 1 |
| refrigerant | | Copper pair 1/4" + 1/2" insulated, 1.5 TR AC GF-MND → SF-AC6 (+ 20 mm PVC drain, 4C x 1.5 sq mm interconnect) | 7.6 | 25.1 | | | 1 |
| refrigerant | | Copper pair 1/4" + 1/2" insulated, 1.5 TR AC GF-GST → GF-O08 (+ 20 mm PVC drain, 4C x 1.5 sq mm interconnect) | 4.6 | 15.2 | | | 1 |

## 3. Wires

| Cable | Circuits | Route m | Cable m (all cores + 10%) | Coils (90 m) / boxes | Conduit | Note |
|---|---|---|---|---|---|---|
| Cat-6 U/UTP (data, from the rack) | 1 | 68.1 | 74.9 | 1 | 20 mm PVC conduit 75 m | 1 run per point + 10% (305 m box) |
| FRLS Cu 1.5 sq mm | 12 | 501.7 | 1655.5 | 19 | 20 mm PVC conduit 552 m | 3 cores (phase, neutral, earth) + 10% |
| FRLS Cu 2.5 sq mm | 10 | 341.3 | 1126.3 | 13 | 20 mm PVC conduit 375 m | 3 cores (phase, neutral, earth) + 10% |
| FRLS Cu 4 sq mm | 15 | 164.9 | 544.1 | 7 | 25 mm PVC conduit 181 m | 3 cores (phase, neutral, earth) + 10% |
| Per maker / vendor (lift, pumps, spare): use 4 sq mm until confirmed | 6 | 107.7 | 355.3 | 4 | 25 mm PVC conduit 118 m | 3 cores (phase, neutral, earth) + 10% |
| SM-1 MTR → DB-1: 4C x 16 sq mm Cu armoured (indicative) | 1 | 23.6 | 26.0 | | 32 mm conduit / buried sleeve | 4-core armoured, buried, sleeved under the lobby floor; clear of the sewer |
| SM-2 DB-1 → DB-2: 4C x 10 sq mm Cu armoured (indicative) | 1 | 9.5 | 10.5 | | 32 mm conduit / buried sleeve | in the GF ceiling slab, up the dresser west wall |
| SM-3 DB-1 → DB-3: 4C x 6 sq mm Cu armoured (indicative) | 1 | 12.1 | 13.4 | | 32 mm conduit / buried sleeve | in the GF ceiling slab, then a riser in the east-wall chase (guest room / bedroom 3 / servant room) |

| | | | | | | |
|---|---|---|---|---|---|---|
| Accessories: 6 A sockets 27, 16 A 4, USB 2, TV 6, data 2, IP65 5, switchboards 16, bedside / 2-way 13 | | | | | modular | |
| Distribution boards: DB-1 21 circuits (26 ways with 20% spare), DB-2 14 circuits (17 ways with 20% spare), DB-3 8 circuits (10 ways with 20% spare) | | | | | DB-1 TPN | RCDs per the circuit list in services_report.txt |

## 4. Paint

| Floor | Room / area | Surface | Area m2 | Area sq ft | Putty kg (2 coats) | Primer L (1 coat) | Emulsion L (2 coats) |
|---|---|---|---|---|---|---|---|
| GF | Kitchen | Interior walls | 36.77 | 396 | 29.4 | 3.7 | 5.7 |
| GF | Kitchen | Ceiling (on POP) | 15.91 | 171 | | 1.6 | 2.5 |
| GF | Dining | Interior walls | 22.3 | 240 | 17.8 | 2.2 | 3.5 |
| GF | Dining | Ceiling (on POP) | 13.8 | 149 | | 1.4 | 2.1 |
| GF | Family Lounge | Interior walls | 15.85 | 171 | 12.7 | 1.6 | 2.5 |
| GF | Family Lounge | Ceiling (on POP) | 16.59 | 179 | | 1.7 | 2.6 |
| GF | Lobby | Ceiling (on POP) | 12.7 | 137 | | 1.3 | 2.0 |
| GF | Toilet | Ceiling (on POP) | 8.37 | 90 | | 0.8 | 1.3 |
| GF | Guest Room | Interior walls | 40.17 | 432 | 32.1 | 4.0 | 6.2 |
| GF | Guest Room | Ceiling (on POP) | 18.73 | 202 | | 1.9 | 2.9 |
| GF | Entrance Foyer | Ceiling (on POP) | 5.59 | 60 | | 0.6 | 0.9 |
| GF | Guest Lounge / Study | Ceiling (on POP) | 13.64 | 147 | | 1.4 | 2.1 |
| GF | Under-stair Storage | Interior walls | 21.37 | 230 | 17.1 | 2.1 | 3.3 |
| FF | Master Washroom | Ceiling (on POP) | 5.11 | 55 | | 0.5 | 0.8 |
| FF | Dresser | Interior walls | 24.93 | 268 | 19.9 | 2.5 | 3.9 |
| FF | Dresser | Ceiling (on POP) | 8.12 | 87 | | 0.8 | 1.3 |
| FF | Master Bedroom | Interior walls | 37.91 | 408 | 30.3 | 3.8 | 5.9 |
| FF | Master Bedroom | Ceiling (on POP) | 25.56 | 275 | | 2.6 | 4.0 |
| FF | Bedroom 3 Toilet | Ceiling (on POP) | 6.36 | 68 | | 0.6 | 1.0 |
| FF | Lobby | Interior walls | 21.58 | 232 | 17.3 | 2.2 | 3.3 |
| FF | Lobby | Ceiling (on POP) | 9.22 | 99 | | 0.9 | 1.4 |
| FF | Bedroom 3 | Interior walls | 49.76 | 536 | 39.8 | 5.0 | 7.7 |
| FF | Bedroom 3 | Ceiling (on POP) | 25.38 | 273 | | 2.5 | 3.9 |
| FF | Kids Room | Interior walls | 41.16 | 443 | 32.9 | 4.1 | 6.4 |
| FF | Kids Room | Ceiling (on POP) | 21.05 | 227 | | 2.1 | 3.3 |
| FF | Kids Toilet | Ceiling (on POP) | 4.65 | 50 | | 0.5 | 0.7 |
| SF | Lobby | Interior walls | 20.14 | 217 | 16.1 | 2.0 | 3.1 |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| SF | Lobby | Ceiling (on POP) | 9.22 | 99 | | 0.9 | 1.4 |
| SF | Servant Washroom | Ceiling (on POP) | 2.43 | 26 | | 0.2 | 0.4 |
| SF | Store | Ceiling (on POP) | 3.64 | 39 | | 0.4 | 0.6 |
| SF | Servant Room | Interior walls | 29.52 | 318 | 23.6 | 3.0 | 4.6 |
| SF | Servant Room | Ceiling (on POP) | 9.46 | 102 | | 0.9 | 1.5 |
| ALL | Exterior façade, parapets, boundary walls | Exterior (party walls excluded) | 254.37 | 2738 | | 30.5 | 50.9 |

## 5. POP (false ceiling)

| Floor | Room | Ceiling | Height mm | Area m2 | Area sq ft | Gypsum boards 1800 × 1200 | Perimeter channel m | Cove m |
|---|---|---|---|---|---|---|---|---|
| GF | Kitchen | POP | 2750 | 15.91 | 171 | 9 | 17.2 | 17.2 |
| GF | Dining | POP | 2750 | 13.8 | 149 | 8 | 9.0 | 9.0 |
| GF | Family Lounge | POP | 2750 | 16.59 | 179 | 9 | 11.6 | 11.6 |
| GF | Lobby | POP | 2750 | 12.7 | 137 | 7 | 13.7 | 13.7 |
| GF | Toilet | POP | 2600 | 8.37 | 90 | 5 | 12.7 | |
| GF | Guest Room | POP | 2750 | 18.73 | 202 | 10 | 17.5 | 17.5 |
| GF | Entrance Foyer | POP + walnut veneer | 2750 | 5.59 | 60 | 3 | 9.7 | 9.7 |
| GF | Guest Lounge / Study | POP | 2750 | 13.64 | 147 | 7 | 15.0 | 15.0 |
| FF | Master Washroom | POP | 2600 | 5.11 | 55 | 3 | 9.4 | |
| FF | Dresser | POP | 2750 | 8.12 | 87 | 5 | 11.4 | 11.4 |
| FF | Master Bedroom | POP | 2750 | 25.56 | 275 | 14 | 22.0 | 22.0 |
| FF | Bedroom 3 Toilet | POP | 2600 | 6.36 | 68 | 4 | 10.4 | |
| FF | Lobby | POP | 2750 | 9.22 | 99 | 5 | 11.2 | 11.2 |
| FF | Bedroom 3 | POP | 2750 | 25.38 | 273 | 13 | 21.7 | 21.7 |
| FF | Kids Room | POP | 2750 | 21.05 | 227 | 11 | 20.5 | 20.5 |
| FF | Kids Toilet | POP | 2600 | 4.65 | 50 | 3 | 9.2 | |
| SF | Lobby | POP | 2750 | 9.22 | 99 | 5 | 12.3 | |
| SF | Servant Washroom | POP | 2600 | 2.43 | 26 | 2 | 6.4 | |
| SF | Store | POP | 2600 | 3.64 | 39 | 2 | 7.6 | |
| SF | Servant Room | POP | 2750 | 9.46 | 102 | 5 | 12.8 | |

## 6. Granite & stone

| Floor | Item | Description | Net m2 | Net sq ft | Wastage % | Note |
|---|---|---|---|---|---|---|
| GF | Kitchen | Backsplash 600 mm (white marble as designed; or granite to match) | 5.82 | 63 | 10 | |
| GF | Under-stair Storage | Floor (flamed granite) | 4.75 | 51 | 10 | |

| | | | | | | |
|---|---|---|---|---|---|---|
| GF | Entrance Court | Paving (flamed granite) | 8.34 | 90 | 10 | |
| GF | Foyer step | Paving (flamed granite) | 0.54 | 6 | 10 | |
| GF | Parking | Cobble setts (granite), ramp / court | 7.31 | 79 | 10 | |
| GF | Ramp (outside plot) | Cobble setts (granite), ramp / court | 4.95 | 53 | 10 | |
| GF-SF | Stair | 32 treads (with 25 mm nosing), 30 mm | 9.28 | 100 | 10 | or Italian marble to match the lobby |
| GF-SF | Stair | 36 risers, 18 mm | 6.96 | 75 | 10 | |
| GF-SF | Stair | 2 mid-landings | 5.66 | 61 | 10 | |
| GF | GF-K01 GF-KIT | Counter top 20 mm, black granite, front edge moulded 2.02 m | 1.21 | 13 | 10 | |
| GF | GF-K02 GF-KIT | Counter top 20 mm, black granite, front edge moulded 2.60 m | 1.56 | 17 | 10 | |
| GF | GF-K03 GF-KIT | Counter top 20 mm, black granite, front edge moulded 2.99 m; hob cut-out | 1.79 | 19 | 10 | |
| GF | GF-K10 GF-KIT | Counter top 20 mm, black granite, front edge moulded 2.10 m; sink cut-out | 1.26 | 14 | 10 | |
| FF | FF-L01 FF-LOB | Counter top 20 mm, black granite, front edge moulded 1.50 m | 0.9 | 10 | 10 | |
| SF | SF-U02 SF-TRB | Counter top 20 mm, black granite, front edge moulded 1.00 m; sink cut-out | 0.6 | 6 | 10 | |
| SF | SF-U03 SF-TRB | Counter top 20 mm, black granite, front edge moulded 1.10 m | 0.5 | 5 | 10 | |
| GF | GF-GL4 | Window sill 1460 × 200 mm, 18 mm | 0.292 | 3.1 | 10 | |
| GF | GF-GL5a | Door threshold 2200 × 150 mm, 18 mm | 0.33 | 3.6 | 10 | |
| GF | GF-GL5b | Window sill 3000 × 200 mm, 18 mm | 0.6 | 6.5 | 10 | |
| GF | GF-GL3 | Window sill 1150 × 350 mm, 18 mm | 0.403 | 4.3 | 10 | |
| GF | GF-KW1 | Window sill 500 × 350 mm, 18 mm | 0.175 | 1.9 | 10 | |
| GF | GF-D3a | Door threshold 800 × 150 mm, 18 mm | 0.12 | 1.3 | 10 | |
| GF | GF-D2a | Door threshold 1000 × 150 mm, 18 mm | 0.15 | 1.6 | 10 | |
| GF | GF-GL1 | Window sill 2400 × 200 mm, 18 mm | 0.48 | 5.2 | 10 | |
| GF | GF-KD1 | Door threshold 1000 × 150 mm, 18 mm | 0.15 | 1.6 | 10 | |
| GF | GF-D3b | Door threshold 800 × 180 mm, 18 mm | 0.144 | 1.6 | 10 | |
| GF | GF-D2b | Door threshold 1000 × 180 mm, 18 mm | 0.18 | 1.9 | 10 | |
| GF | GF-D1 | Door threshold 1450 × 180 mm, 18 mm | 0.261 | 2.8 | 10 | |
| GF | GF-GL2 | Window sill 2770 × 230 mm, 18 mm | 0.637 | 6.9 | 10 | |
| GF | GF-GD1 | Door threshold 1200 × 60 mm, 18 mm | 0.072 | 0.8 | 10 | |
| GF | GF-GL6d | Door threshold 700 × 10 mm, 18 mm | 0.007 | 0.1 | 10 | |
| FF | FF-GL4 | Window sill 1460 × 200 mm, 18 mm | 0.292 | 3.1 | 10 | |
| FF | FF-MW1 | Window sill 500 × 350 mm, 18 mm | 0.175 | 1.9 | 10 | |
| FF | FF-GL3 | Window sill 1150 × 350 mm, 18 mm | 0.403 | 4.3 | 10 | |
| FF | FF-GL7a | Door threshold 2200 × 150 mm, 18 mm | 0.33 | 3.6 | 10 | |
| FF | FF-GL7b | Window sill 1300 × 200 mm, 18 mm | 0.26 | 2.8 | 10 | |

| | | | | | | |
|---|---|---|---|---|---|---|
| FF | FF-D2a | Door threshold 1000 × 150 mm, 18 mm | 0.15 | 1.6 | 10 | |
| FF | FF-D3a | Door threshold 800 × 150 mm, 18 mm | 0.12 | 1.3 | 10 | |
| FF | FF-D2b | Door threshold 1000 × 180 mm, 18 mm | 0.18 | 1.9 | 10 | |
| FF | FF-D2c | Door threshold 1000 × 150 mm, 18 mm | 0.15 | 1.6 | 10 | |
| FF | FF-D3b | Door threshold 800 × 150 mm, 18 mm | 0.12 | 1.3 | 10 | |
| FF | FF-D2d | Door threshold 1000 × 150 mm, 18 mm | 0.15 | 1.6 | 10 | |
| FF | FF-D3c | Door threshold 800 × 150 mm, 18 mm | 0.12 | 1.3 | 10 | |
| FF | FF-GL1 | Window sill 2400 × 200 mm, 18 mm | 0.48 | 5.2 | 10 | |
| FF | FF-GL10 | Window sill 1000 × 350 mm, 18 mm | 0.35 | 3.8 | 10 | |
| FF | FF-GL6ad | Door threshold 700 × 10 mm, 18 mm | 0.007 | 0.1 | 10 | |
| FF | FF-GL6bd | Door threshold 700 × 10 mm, 18 mm | 0.007 | 0.1 | 10 | |
| SF | SF-PD1a | Door threshold 1000 × 180 mm, 18 mm | 0.18 | 1.9 | 10 | |
| SF | SF-PW1 | Window sill 1200 × 200 mm, 18 mm | 0.24 | 2.6 | 10 | |
| SF | SF-PD1b | Door threshold 1000 × 150 mm, 18 mm | 0.15 | 1.6 | 10 | |
| SF | SF-PD2a | Door threshold 800 × 150 mm, 18 mm | 0.12 | 1.3 | 10 | |
| SF | SF-PD2b | Door threshold 800 × 150 mm, 18 mm | 0.12 | 1.3 | 10 | |
| SF | SF-PD2c | Door threshold 800 × 150 mm, 18 mm | 0.12 | 1.3 | 10 | |
| SF | SF-GL3 | Window sill 1150 × 350 mm, 18 mm | 0.403 | 4.3 | 10 | |

## 7. Timber & veneer

| Floor | Item | Description | Unit | Qty | sq ft | Note |
|---|---|---|---|---|---|---|
| GF | Family Lounge | Fluted walnut feature wall (veneered MDF flutes on ply) | m2 | 6.32 | 68 | |
| GF | Lobby | Walnut veneer wall cladding (PDF schedule) | m2 | 23.99 | 258 | |
| GF | Entrance Foyer | Walnut veneer wall cladding (PDF schedule) | m2 | 6.99 | 75 | |
| GF | Entrance Foyer | Fluted walnut feature wall (veneered MDF flutes on ply) | m2 | 8.01 | 86 | |
| GF | Entrance Foyer | Walnut veneer ceiling accent (with the POP) | m2 | 1.68 | 18 | about 30% of the ceiling |
| GF | Guest Lounge / Study | Walnut veneer wall cladding (PDF schedule) | m2 | 32.55 | 350 | |
| FF | Master Bedroom | Fluted walnut feature wall (veneered MDF flutes on ply) | m2 | 10.63 | 114 | |
| GF | GF-D3a | Door: frame 125 × 60 mm sal / hardwood, 1 shutter(s) 800 × 2400 × 35 mm flush, veneer both faces | frame cft | 1.48 | | 5.60 m frame |
| GF | GF-D2a | Door: frame 125 × 60 mm sal / hardwood, 1 shutter(s) 1000 × 2400 × 35 mm flush, veneer both faces | frame cft | 1.54 | | 5.80 m frame |
| GF | GF-D3b | Door: frame 125 × 60 mm sal / hardwood, 1 shutter(s) 800 × 2400 × 35 mm flush, veneer both faces | frame cft | 1.48 | | 5.60 m frame |

| | | | | | | |
|---|---|---|---|---|---|---|
| GF | GF-D2b | Door: frame 125 × 60 mm sal / hardwood, 1 shutter(s) 1000 × 2400 × 35 mm flush, veneer both faces | frame cft | 1.54 | | 5.80 m frame |
| GF | GF-D1 | Main door: frame 125 × 60 mm teak, 2 shutter(s) 725 × 2400 × 40 mm solid teak panelled | frame cft | 1.66 | | 6.25 m frame |
| FF | FF-D2a | Door: frame 125 × 60 mm sal / hardwood, 1 shutter(s) 1000 × 2400 × 35 mm flush, veneer both faces | frame cft | 1.54 | | 5.80 m frame |
| FF | FF-D3a | Door: frame 125 × 60 mm sal / hardwood, 1 shutter(s) 800 × 2400 × 35 mm flush, veneer both faces | frame cft | 1.48 | | 5.60 m frame |
| FF | FF-D2b | Door: frame 125 × 60 mm sal / hardwood, 1 shutter(s) 1000 × 2400 × 35 mm flush, veneer both faces | frame cft | 1.54 | | 5.80 m frame |
| FF | FF-D2c | Door: frame 125 × 60 mm sal / hardwood, 1 shutter(s) 1000 × 2400 × 35 mm flush, veneer both faces | frame cft | 1.54 | | 5.80 m frame |
| FF | FF-D3b | Door: frame 125 × 60 mm sal / hardwood, 1 shutter(s) 800 × 2400 × 35 mm flush, veneer both faces | frame cft | 1.48 | | 5.60 m frame |
| FF | FF-D2d | Door: frame 125 × 60 mm sal / hardwood, 1 shutter(s) 1000 × 2400 × 35 mm flush, veneer both faces | frame cft | 1.54 | | 5.80 m frame |
| FF | FF-D3c | Door: frame 125 × 60 mm sal / hardwood, 1 shutter(s) 800 × 2400 × 35 mm flush, veneer both faces | frame cft | 1.48 | | 5.60 m frame |
| SF | SF-PD2a | Door: frame 125 × 60 mm sal / hardwood, 1 shutter(s) 800 × 2400 × 35 mm flush, veneer both faces | frame cft | 1.48 | | 5.60 m frame |
| SF | SF-PD2b | Door: frame 125 × 60 mm sal / hardwood, 1 shutter(s) 800 × 2400 × 35 mm flush, veneer both faces | frame cft | 1.48 | | 5.60 m frame |
| SF | SF-PD2c | Door: frame 125 × 60 mm sal / hardwood, 1 shutter(s) 800 × 2400 × 35 mm flush, veneer both faces | frame cft | 1.48 | | 5.60 m frame |
| GF | Pergola | 4 posts 150×150×2.9 m, beam 100×250×6.7 m, ledger 100×200×6.8 m, 15 rafters 60×200×2.63 m | cft | 36.5 | | hardwood, walnut stain, outdoor PU |
| GF-SF | Stair handrail | Walnut handrail 60 × 50 mm on the spine | m | 13.0 | 42.6 | |
| GF | GF-F25 (mandir) | Fluted cabinet 1.1 × 0.47 × 0.45 m (veneered MDF) + marble back panel 1.1 × 2.4 m (stone) | nos | 1 | | |
| GF | GF-O12 (tulsi backdrop) | Fluted walnut cladding, exterior grade, PU | m2 | 3.04 | 33 | |

## 8. MDF board (wardrobes and storage)

| Floor | Id | Unit | Room | Size w x d x h mm | Board | Carcass m2 | Shutters m2 | Back 8 mm m2 | Sheets 18/19 mm (8×4, +15%) | Sheets 8 mm | Shutters (desks / dressers: drawers) | Soft-close hinges | Edge band m | Laminate m2 (shutter faces) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| GF | GF-K01 | Kitchen / pantry base unit | GF-KIT | 2020 x 600 x 900 | MDF 18 mm | 5.68 | 1.72 | 1.72 | 3 | 1 | 4 | 8 | 20.3 | 1.89 |

| | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| GF | GF-K02 | Kitchen / pantry base unit | GF-KIT | 2600 x 600 x 900 | MDF 18 mm | 6.72 | 2.21 | 2.21 | 4 | 1 | 5 | 10 | 24.9 | 2.43 |
| GF | GF-K03 | Kitchen / pantry base unit | GF-KIT | 2986 x 600 x 900 | MDF 18 mm | 7.92 | 2.54 | 2.54 | 5 | 1 | 6 | 12 | 29.4 | 2.79 |
| GF | GF-K05 | Wall cabinet | GF-KIT | 2986 x 350 x 750 | MDF 18 mm | 4.45 | 2.24 | 2.24 | 3 | 1 | 6 | 12 | 27.7 | 2.46 |
| GF | GF-K09 | Wall cabinet | GF-KIT | 2600 x 350 x 750 | MDF 18 mm | 3.78 | 1.95 | 1.95 | 3 | 1 | 5 | 10 | 23.5 | 2.15 |
| GF | GF-F21 | Shoe console | GF-FOY | 1800 x 450 x 900 | MDF 18 mm | 3.65 | 1.62 | 1.62 | 3 | 1 | 4 | 8 | 18.9 | 1.78 |
| GF | GF-G04 | Wardrobe | GF-GST | 3970 x 600 x 2700 | MDF 18 mm | 24.01 | 10.72 | 10.72 | 14 | 5 | 7 | 28 | 85.8 | 11.79 |
| GF | GF-T03 | Vanity | GF-TLT | 900 x 600 x 850 | BWP ply 19 mm (wet) | 2.16 | 0.41 | 0.41 | 1 | 1 | 2 | 4 | 7.2 | 0.45 |
| GF | GF-F04 | TV unit | GF-DRW | 1800 x 400 x 450 | MDF 18 mm | 2.7 | 0.81 | 0.81 | 2 | 1 | 4 | 8 | 13.9 | 0.89 |
| GF | GF-F19 | Crockery unit | GF-DRW | 1400 x 450 x 2100 | MDF 18 mm | 6.62 | 2.94 | 2.94 | 4 | 2 | 3 | 12 | 30.1 | 3.23 |
| GF | GF-F24 | Vanity | GF-DIN | 700 x 450 x 850 | BWP ply 19 mm (wet) | 1.35 | 0.32 | 0.32 | 1 | 1 | 2 | 4 | 6.2 | 0.35 |
| GF | GF-K10 | Kitchen / pantry base unit | GF-KIT | 2100 x 600 x 900 | BWP ply 19 mm (wet) | 5.82 | 1.78 | 1.78 | 3 | 1 | 4 | 8 | 20.7 | 1.96 |
| GF | GF-K13 | Wall cabinet | GF-KIT | 2100 x 350 x 700 | MDF 18 mm | 3.18 | 1.47 | 1.47 | 2 | 1 | 4 | 8 | 18.9 | 1.62 |
| GF | GF-M01 | Study desk | GF-MND | 1400 x 600 x 750 | MDF 18 mm | 3.87 | 0.28 | 1.05 | 2 | 1 | 0 | 0 | 9.6 | 0.31 |
| GF | GF-M04 | TV unit | GF-MND | 1500 x 400 x 450 | MDF 18 mm | 2.34 | 0.68 | 0.68 | 2 | 1 | 3 | 6 | 11.5 | 0.74 |

| | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| GF | GF-J01 | Tall storage | GF-JAN | 800 x 600 x 2250 | MDF 18 mm | 5.58 | 1.8 | 1.8 | 3 | 1 | 2 | 8 | 19.9 | 1.98 |
| GF | GF-J02 | Tall storage | GF-JAN | 800 x 600 x 1600 | MDF 18 mm | 3.36 | 1.28 | 1.28 | 2 | 1 | 2 | 6 | 13.6 | 1.41 |
| GF | GF-J05 | Tall storage | GF-JAN | 500 x 450 x 1400 | MDF 18 mm | 1.94 | 0.7 | 0.7 | 2 | 1 | 1 | 3 | 8.1 | 0.77 |
| GF | GF-J04 | Tall storage | GF-JAN | 1100 x 600 x 1400 | MDF 18 mm | 4.5 | 1.54 | 1.54 | 3 | 1 | 2 | 6 | 15.3 | 1.69 |
| GF | GF-K04 | Kitchen tall unit | GF-KIT | 800 x 600 x 2250 | MDF 18 mm | 5.58 | 1.8 | 1.8 | 3 | 1 | 2 | 8 | 19.9 | 1.98 |
| GF | GF-K12 | Tall storage | GF-KIT | 400 x 600 x 2250 | MDF 18 mm | 4.14 | 0.9 | 0.9 | 2 | 1 | 1 | 4 | 12.2 | 0.99 |
| FF | FF-M04 | Wardrobe | FF-MST | 2056 x 600 x 2700 | MDF 18 mm | 13.88 | 5.55 | 5.55 | 8 | 3 | 4 | 16 | 48.8 | 6.11 |
| FF | FF-M05 | Wardrobe | FF-MST | 1127 x 600 x 2700 | MDF 18 mm | 8.92 | 3.04 | 3.04 | 5 | 2 | 2 | 8 | 27.9 | 3.35 |
| FF | FF-B01 | Wardrobe | FF-BD3 | 2038 x 600 x 2700 | MDF 18 mm | 13.82 | 5.5 | 5.5 | 8 | 3 | 4 | 16 | 48.7 | 6.05 |
| FF | FF-B11 | Wardrobe | FF-BD3 | 897 x 600 x 2700 | MDF 18 mm | 6.47 | 2.42 | 2.42 | 4 | 1 | 2 | 8 | 23.4 | 2.66 |
| FF | FF-B05 | Dresser | FF-BD3 | 1200 x 450 x 750 | MDF 18 mm | 2.63 | 0.24 | 0.9 | 2 | 1 | 0 | 0 | 8.7 | 0.26 |
| FF | FF-B08 | Storage bench | FF-BD3 | 2400 x 450 x 450 | MDF 18 mm | 4.05 | 1.08 | 1.08 | 2 | 1 | 5 | 10 | 18.3 | 1.19 |
| FF | FF-T22 | Vanity | FF-TL3 | 900 x 600 x 850 | BWP ply 19 mm (wet) | 2.16 | 0.41 | 0.41 | 1 | 1 | 2 | 4 | 7.2 | 0.45 |
| FF | FF-K01 | Wardrobe | FF-KID | 4550 x 553 x 2700 | MDF 18 mm | 25.55 | 12.29 | 12.29 | 15 | 5 | 8 | 32 | 98.5 | 13.51 |

| | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| FF | FF-K06 | Study desk | FF-KID | 1600 x 600 x 750 | MDF 18 mm | 4.23 | 0.32 | 1.2 | 2 | 1 | 0 | 0 | 10.7 | 0.35 |
| FF | FF-L01 | Kitchen / pantry base unit | FF-LOB | 1500 x 600 x 900 | MDF 18 mm | 4.23 | 1.27 | 1.27 | 3 | 1 | 3 | 6 | 15.2 | 1.4 |
| FF | FF-L05 | Wall cabinet | FF-LOB | 1500 x 350 x 750 | MDF 18 mm | 2.36 | 1.12 | 1.12 | 2 | 1 | 3 | 6 | 14.2 | 1.24 |
| FF | FF-T11 | Vanity | FF-KTL | 1065 x 600 x 850 | BWP ply 19 mm (wet) | 2.73 | 0.48 | 0.48 | 2 | 1 | 2 | 4 | 8.5 | 0.53 |
| FF | FF-K07 | Tall storage | FF-KID | 1200 x 450 x 2400 | MDF 18 mm | 6.48 | 2.88 | 2.88 | 4 | 2 | 3 | 12 | 31.2 | 3.17 |
| FF | FF-T04 | Vanity | FF-MTL | 1000 x 550 x 850 | BWP ply 19 mm (wet) | 2.39 | 0.45 | 0.45 | 2 | 1 | 2 | 4 | 8.1 | 0.5 |
| FF | FF-D01 | Dressing table | FF-DRS | 1100 x 450 x 750 | MDF 18 mm | 2.5 | 0.22 | 0.83 | 2 | 1 | 0 | 0 | 8.2 | 0.24 |
| FF | FF-D02 | Wardrobe | FF-DRS | 1700 x 600 x 2700 | MDF 18 mm | 10.98 | 4.59 | 4.59 | 7 | 2 | 3 | 12 | 37.9 | 5.05 |
| FF | FF-D03 | Wardrobe | FF-DRS | 560 x 600 x 2700 | MDF 18 mm | 5.26 | 1.51 | 1.51 | 3 | 1 | 1 | 4 | 15.3 | 1.66 |
| FF | FF-D05 | Wardrobe | FF-DRS | 800 x 600 x 2700 | MDF 18 mm | 6.12 | 2.16 | 2.16 | 4 | 1 | 2 | 8 | 22.6 | 2.38 |
| FF | FF-D06 | Storage bench | FF-DRS | 1460 x 450 x 450 | MDF 18 mm | 2.58 | 0.66 | 0.66 | 2 | 1 | 3 | 6 | 11.3 | 0.72 |
| FF | FF-M06 | TV unit | FF-MST | 1800 x 400 x 450 | MDF 18 mm | 2.7 | 0.81 | 0.81 | 2 | 1 | 4 | 8 | 13.9 | 0.89 |
| SF | SF-S02 | Wardrobe | SF-SRV | 1000 x 600 x 2100 | MDF 18 mm | 7.38 | 2.1 | 2.1 | 4 | 1 | 2 | 8 | 22.7 | 2.31 |
| SF | SF-S03 | Desk | SF-SRV | 900 x 500 x 750 | MDF 18 mm | 2.1 | 0.18 | 0.68 | 1 | 1 | 0 | 0 | 6.4 | 0.2 |

| | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| SF | SF-U02 | Utility Counter | SF-TRB | 1000 x 600 x 900 | BWP ply 19 mm (wet) | 3.33 | 0.85 | 0.85 | 2 | 1 | 2 | 4 | 11.0 | 0.94 |
| SF | SF-U04 | Tall storage | SF-TRB | 600 x 600 x 2100 | BWP ply 19 mm (wet) | 4.68 | 1.26 | 1.26 | 3 | 1 | 2 | 8 | 17.4 | 1.39 |
| SF | SF-S11 | Tall storage | SF-WSH | 1400 x 600 x 2400 | MDF 18 mm | 9.36 | 3.36 | 3.36 | 5 | 2 | 3 | 12 | 32.8 | 3.7 |

## 9. Lights & fittings

| Fitting | Qty | Unit | Where |
|---|---|---|---|
| Downlight fixtures, 10 W slim COB 3000 K, cut-out 75 mm, on the ~1.4 m grid shown in the 3D (each light point above switches a group) | 88 | nos | GF-KIT 7, GF-DIN 8, GF-DRW 8, GF-LOB 5, GF-TLT 2, GF-GST 6, GF-FOY 2, GF-MND 6, FF-MTL 1, FF-DRS 2, FF-MST 9, FF-TL3 2, FF-LOB 3, FF-BD3 9, FF-KID 9, FF-KTL 2, SF-LOB 3, SF-SWR 1, SF-WSH 1, SF-SRV 2 |
| Light points (switched groups, per the electrical sheet); wet rooms IP44 | 36 | nos | FF-BD3 2, FF-DRS 1, FF-KID 2, FF-KTL 1, FF-LOB 2, FF-MST 3, FF-MTL 2, FF-TL3 1, GF-DIN 2, GF-DRW 2, GF-FOY 2, GF-GST 2, GF-JAN 1, GF-KIT 2, GF-LOB 2, GF-MND 2, GF-TLT 2, SF-LOB 2, SF-SRV 1, SF-SWR 1, SF-WSH 1 |
| Statement pendant (dining) | 1 | nos | GF-DIN 1 |
| Mirror light 600 mm, IP44 | 4 | nos | FF-DRS 1, FF-MTL 1, FF-TL3 1, GF-DIN 1 |
| Wall / niche light (IP65 outdoors) | 10 | nos | FF-BAL 2, GF-COURT 2, GF-DECK 2, GF-DRW 1, GF-LAWN-B 1, SF-TRB 2 |
| Garden bollard, 7 W, IP65 | 8 | nos | FF-BAL 2, GF-COURT 2, GF-LAWN-B 4 |
| Ceiling fan, BLDC 1200 mm | 7 | nos | FF-BD3 1, FF-KID 1, FF-MST 1, GF-DRW 1, GF-GST 1, GF-MND 1, SF-SRV 1 |
| Exhaust fan 200 mm | 7 | nos | FF-KTL 1, FF-MTL 1, FF-TL3 1, GF-KIT 2, GF-TLT 1, SF-SWR 1 |
| Smoke detector | 10 | nos | FF-BD3 1, FF-KID 1, FF-LOB 1, FF-MST 1, GF-DRW 1, GF-GST 1, GF-LOB 1, GF-MND 1, SF-LOB 1, SF-SRV 1 |
| Heat detector (kitchen) | 1 | nos | GF-KIT 1 |
| LED strip under wall cabinets, 10 W/m 3000 K, aluminium profile | 9.2 | m | 4 runs |
| Cove LED strip, 12 W/m 2700 K, in POP coves | 180.6 | m | + 37 drivers (1 per 5 m) |

## 10. uPVC doors & windows (rear wall)

| Floor | Id | Item | Size w x h mm | Frame + sash lines m | Glass m2 (solar-control DGU) | of which laminated (fixed) m2 | Mosquito mesh m2 | MS grille m2 | Grille kg (approx.) | Note |
|---|---|---|---|---|---|---|---|---|---|---|
| GF | GF-GL5a | GL-5a Sliding door, 2 sashes (one fixed), 3 tracks | 2200 x 2400 | 11.6 | 5.28 | 2.64 | 2.64 | 2.64 | 37.0 | grille inside, sliding, parks behind the fixed sash |
| GF | GF-GL5b | GL-5b Window: fixed lite + 2 sliding sashes, 3 tracks | 3000 x 1500 | 12.0 | 4.5 | 1.12 | 3.38 | 4.5 | 63.0 | grille outside, fixed |

| | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| FF | FF-GL7a | GL-7a Sliding door, 2 sashes (one fixed), 3 tracks | 2200 x 2400 | 11.6 | 5.28 | 2.64 | 2.64 | 2.64 | 37.0 | grille inside, sliding, parks behind the fixed sash |
| FF | FF-GL7b | GL-7b Window: fixed lite + 2 sliding sashes, 3 tracks | 1300 x 1500 | 8.6 | 1.95 | 0.0 | 1.95 | 1.95 | 27.0 | grille outside, fixed |

## How it is measured

How the quantities are measured (all from house_r1.json):

- Floors: room polygons (net). Option A Italian marble +15% wastage; Option B 1600 × 800 vitrified +8%, 2 tiles per box. Skirting = walled perimeter minus doors.

- Tiles: washroom walls full height to the 2.6 m false ceiling, minus doors and windows, +10%. Waterproofing = floor + 300 mm up the walls (more in the shower: 1.8 m).

- Paint: interior walls to the false ceiling minus openings, tiles, veneer cladding, fluted walls and the kitchen backsplash; ceilings = POP area; exterior = non-party external walls x storey height, parapets and boundary walls (both faces where both are exposed). Coverage rates are indicative.

- POP: ceilings of type POP (gypsum board 12.5 mm on GI framing, POP-finished), boards +10%; cove length = room perimeter where the ceiling has a cove.

- Granite: counter tops (20 mm black granite, moulded front), sills on every window (wall + 50 mm), thresholds on every door, stair treads / risers / landings (or marble to match the lobby), flamed granite paving. +10% wastage.

- Timber: door frames 125 × 60 mm (teak for the main door), shutters 35 mm flush with veneer (main door 40 mm teak); pergola hardwood; handrail; walnut veneer cladding (lobby, foyer, guest lounge, per the PDF schedule) and fluted walnut feature walls.

- MDF: each wardrobe / storage unit = carcass (sides, top, bottom, a vertical every 900 mm, 4 shelves if tall) + shutters (18 mm) + back (8 mm); +15% on 8 × 4 ft sheets. BWP ply for the vanities, the utility counter, the kitchen sink base and units on the terrace (owner: MDF elsewhere).

- Lights: counts from the electrical points; cove LED = cove length; under-cabinet LED = the cabinet runs.

- Pipes: lengths along the modelled routes and stacks, 3 m lengths +10%; bends counted where a route changes direction (tees and couplers extra).

- Wires: route length of each circuit x 3 cores (phase, neutral, earth) +10%; 90 m coils; sub-main sizes indicative (electrician to size).

- uPVC (F18, F21): the GF rear-wall and FF master-balcony doors and windows only: heavy-series steel-reinforced uPVC, 3 tracks (2 glass + mesh), solar-control double glazing, laminated in the fixed lites; door with multi-point lock and a recessed bottom track; MS grilles powder-coated black. The other windows are not in this take-off.

Not included: labour, adhesives other than noted, hardware beyond hinges, sanitaryware, glass and windows other than the uPVC rear wall, the lift, ACs and appliances.